

CORRIGENDUM-III

Name of Work: Providing, Supplying & Fixing CFRP Laminate or Wrapping of approved manufacturer on some damaged locations of Rabindra Setu.”

Ref.I) NIT No. _ SMPK/KDS/CIV /T/2579/17 dt. 14.06.2021

II) CORRIGENDUM-I SMPK/KDS/CIV /T/2579/726 dt. 28.06.2021

III) CORRIGENDUM-II SMPK/KDS/CIV /T/2579/774 dt. 06.07.2021

With reference to the above NIT and Corrigendum the following Corrigendum-III is being issued.

Sl. No	Page Ref.	Methodology of Work
1.	Page No. 18(Scope of Work) Page No. 44 & 45 (Price Bid ,Item No.2 and 3)	In addition to previous Scope of work for Item no. 2 and 3 of BOQ the following Methodology shall be used in Rivet Locations. 1. Cut strips of width equal to the clear spacing. 2. Paste in two perpendicular directions in between the rivets. 3. Paste carbon fibre in the other areas without rivet. 4. Paste carbon fibre for the whole area of rivet securing it firmly over the pasted stirrups and rivets. 5. Wherever bulging of wrap is observed, paste one more layer of strip.

All other terms & conditions and Clauses will remain same as per original

Superintending Engineer, Contract
For □□□□□ □□□□□□□□ / Chief Engineer