

No. Mech/EE(CT-II)/1618

By Speed Post

Dated:16.11.2021

Sub: Repairing of damaged, old wooden planks of the Walkway along the 4 sides including Jib and left side of one layer above the Trolley Drive path as well as fixing of broken fiber windows of machine room of 200 T Cantilever Crane.

ट्रॉली ड्राइव पथ के ऊपर एक परत के जिब और बाई ओर के वॉकवे के क्षतिग्रस्त, पुराने लकड़ी के तख्तों की मरम्मत के साथ-साथ 200 टी कैंटिलीवर क्रेन के मशीन रूम की टूटी हुई फाइबर खिड़कियों को ठीक करना।

Dear Sir,

This office requests you to submit your budgetary offer for “Repairing of damaged, old wooden planks of the Walkway along the 4 sides including Jib and left side of one layer above the Trolley Drive path as well as fixing of broken fiber windows of machine room of 200 T Cantilever Crane.”. The scope of work and specification are furnished below:

Scope of work & Specification:

- i) Changing of the old and damaged Planks with new Wooden Planks.
- ii) Proper fixing of New Wooden Planks.
- iii) Double coat Painting of all the newly fixed Wooden Planks i.e Primer and Final Paint.
- iv) Checking of the entire Walkways' Load Bearing Strength after completion of the Job.
- v) Dumping of the old and damaged Planks at the 200 T Crane Store at the Jetty.
- vi) The Wooden Planks should be made of Water Resistant Saal Wood with proper Test Certificate.
- viii) The approximate Dimensions of the Wooden Planks are as follows:
 - (a) 6'' x 36'' x 1.5'' of 225 Pcs (approx.)
 - (b) 6'' x 34'' x 1.5'' of 470 Pcs (approx.)
 - (c) 6'' x 29'' x 1.5'' of 80 Pcs (approx.)
 - (d) 6'' x 25'' x 1.5'' of 60 Pcs (approx.)
 - (e) 1.5'' x 1.5'' x 760' of a single Length of 760 Feet.
- ix) All the broken fiber widows to be re-fixed inside the machine room. The approximate dimension is given below:
 - (a) 7' x 3' of 12 pcs

TERMS AND CONDITIONS:

1. Before submitting the offer the contractor may visit the 200 T crane installed at berth no. 1 of NSD, SMP, Kolkata with prior intimation for taking actual measurement of the sample.
2. Material Test certificate from a Govt. approved Test House to be provided along with the delivery of the material
3. **Guarantee period:** The contractor shall make good at his own expenses of all defects, due to faulty design, materials and workmanship, which may develop during a period of 12 months from the date of supply of the Jaw Plate.
4. **Payment Terms:** 100% payment will be made after completion of job and satisfactory acceptance of the same by Assistance Executive Engineer, GRJ/NSD or his authorized representative.
5. 3% amount of total contractual value will be retained as security Deposit which would be released after successful completion of Guarantee Period.
6. **Completion Period:** 08 weeks from the date of placement of order, this includes procurement of wood and completion of work as per scope of work.
7. **Liquidated Damage:** ½% (half percent) of the order value of each item for every week or part thereof subject to maximum 10% (ten percent) of the order value would be deducted in case you fail to complete the delivery within the stipulated period.

The budgetary offer to be given below:

Sl .No.	Description of work	Lump sum Price (in Rs.) (excluding applicable GST)
1.	Repairing of damaged, old wooden planks of the Walkway along the 4 sides including Jib and left side of one layer above the Trolley Drive path as well as fixing of broken fiber windows of machine room of 200 T Cantilever Crane as per scope of work.	Rs.....
Total offered Price for Repairing of damaged, old wooden planks of the Walkway along the 4 sides including Jib and left side of one layer above the Trolley Drive path as well as fixing of broken fiber windows of machine room of 200 T Cantilever Crane excluding applicable GST (in words): Rupees.....		

You are requested to submit your quotation preferably within 30.11.2021.

(R. K. Biswakarma)
Executive Engineer (CT-II)
For Chief Mechanical Engineer

Copy to (Not in original):

DCME-III - for kind information please.

AEE (GRJ/NSD)- for kind information and necessary action please.