



**KOLKATA PORT TRUST  
HALDIA DOCK COMPLEX**  
Office Of The Sr. Dy. Manager (IZ&R),  
Haldia Dock Complex.  
Operational Building, 2nd Floor, A- Block  
Chiranjibpur, Purba Medinipur - 721604  
Fax - 03224-252110, Ph:- 03224-252854



No. I&CF/IZ&R/Q/ 149

Dated: - 16/06/2015

**QUOTATION FOR EMERGENT WORK OF PROVIDING, FITTING AND FIXING CAUTION BOARDS AT DIFFERENT UNMANNED LEVEL CROSSINGS AND HEIGHT GAUGES UNDER IZ&R SECTION INCLUDING ALLIED WORKS AT HALDIA, HDC.**

Sealed quotations are invited for the subject work from enlisted contractors of I&CF Division, Haldia Dock Complex as per the following terms and conditions, specifications and enclosed bill of quantities.

- (1) Quotations are to be submitted in sealed envelope superscribing the name of the quotation to **Sr.Dy. Manager(IZ&R)'s Office at Chiranjibpur Operational Building, Haldia, HDC within 15:00 Hrs on 19.06.2015** as per details specified in Bill of Quantities and Quotations shall be **opened on the same date after 15:30 Hrs.**
- (2) **Enlisted contractors under I&CF Division, HDC are eligible to participate in the quotation.**
- (3) **The Quotationer shall quote his rate as percentage above / below / at par with the estimated amount put to quotation properly based on his own analysis.**
- (4) The work shall be executed as per the BOQ, G.C.C., workmanship mentioned in PWD Schedule of work and also as per direction of Engineer.
- (5) All Equipments, tools and plants are to be supplied by the quotationer at his own cost.
- (6) The work is urgent in nature and shall have to be commenced immediately on placement of order and shall have to be **completed within 10(ten) days** from the commencement of work .
- (7) The Quotationer shall include in their prices any sum payable as taxes (particularly Sale Tax), Royalty etc. or otherwise to the Govt. or public bodies or individuals and such taxes shall not be an extra charge payable by the Trustees. The bidder shall not include Service Tax in his rates. In case Service Tax is payable, it will be paid extra by the Trustees.
- (8) The bidder must initial any correction in rates.
- (9) Payment will be made based on measurement as stipulated in the bill of quantities as per accepted rate after completion of work.
- (10) The Contractor shall maintain the works allotted to him as per Clause 9.0 of the General Conditions of Contract for a period of **2 (two) months** from the date of completion as certified by the Engineer or his representative in Form G.C. 1.

**( M. K. Acharya.)  
Sr. Dy. Manager (IZ&R),  
I & CF Divn.,  
HALDIA DOCK COMPLEX**

**B.O.Q.**

**Providing, fitting and fixing Caution Boards at different unmanned level crossings and height gauges under IZ&R section including allied works at Haldia, HDC.**

<b>It. No</b>	<b>Description of work</b>	<b>Quantity</b>	<b>Rate (Rs)</b>	<b>Unit</b>	<b>Amount (Rs)</b>
1	Providing, fitting and fixing of Retro-reflecteting Caution Board made of high intensity grade sheeting fixed over aluminium sheet of 2mm thick including lettering, embossing picture etc. all complete as per drawing and direction of Engineer-in-charge.	4.50	7,000.00	SqM	31,500.00
2	Earth work in filling with earth obtained by fresh excavation from land arranged by department within a lead of 200m including watering and ramming etc. layer by layer complete as directed. Payment to be made on the basis of measurement of finished quantity of work.	4.00	120.47	CuM	481.88
3	Earth work in filling with earth obtained from excavation of foundation in layers not exceeding 150mm. including watering and ramming etc. layer by layer complete as directed. Payment to be made on the basis of measurement of finished quantity of work.	30.00	138.55	CuM	4156.50
4	Provide and lay cement concrete (1:3:6) with 20 mm down stonechips in foundation and for rail post grouting in proper line and level all complete and as directed.	1.5	5772.80	CuM	8659.20
5	Provide and lay 15 mm th. cement plaster (1:4) with medium coarse sand to exterior surfaces of walls and columns etc. finished with neat cement punning over the plastered surfaces. Include for necessary curing etc. all complete and as directed.	6	245.30	Sq.M	1471.80
6	Hire and labour charges for shuttering for building works for item no.4 above all complete as directed.	3.6	243.10	SqM	875.16
7	Sort out and take delivery of second hand 90 lbs / yard or 60 Kg. /Mtr. Rails from Trustees PW Store Yards at HDC and loading, transport through road upto a distance of 5 KM, unloading and stacking the same at the site of work, all complete.	1.3	220.00	M.T	286.00

8	Labour for hoisting and placing in proper position (up to 1st floor level) departmental Rails including cutting holes and req.length, fitting and fixing same with bolts and nuts, if necessary (but excluding cost of such bolts and nuts)	1.3	4160.00	M.T	5408.00
9	M.S. structural works in frame work with angle, channel, flats sections connected to one another with bracket, gussets, cleats as per design, direction of Engineer-in-charge complete including cutting to requisite shape and length, fabrication with necessary bolting, metal arc welding using electrodes of approved make and brand, haulage, hoisting and erection all complete. The rate includes the cost of rolled steel section, consumables such as electrodes, gas and hire charge of all tools and plants and labour required for the work including all incidental chages such as electricity charges, labour insurance charges etc. (Payment to be made on the basis of calculated weight of structural members only in finished work as per IS specified weight. Payment for gusset, bracket, cleat, rivets, bolts and nuts to be made by adding the actual weight of such items with the weight of finished structural members.)	0.180	88174.90	MT	15,871.48
10	Provide and apply protective Decorative exterior premium 100% acrylic emulsion paint two coats of Asian / Berger / Nerolac / ICI paint make on old / new concrete / plastered surfaces including scaffolding, scraping, wire brushing and preparing the surfaces.	80.00	101.20	SqM	8,096.00
11	Provide and apply one coat of synthetic oil bound primer of approved quality to steel surface include for scrapping, brushing, sand papering and cleaning the surfaces smooth before application of primer all complete as directed.	22.00	34.10	SqM	750.20
12	Provide and lay paint on steel work with two coats of approved synthetic enamel paint (other than high gloss of approved quality) including scrapping, brushing and cleaning the surfaces if necessary all complete as directed.	142.00	84.70	SqM	12,027.40
<b>Total = Rs. 89583.62</b>					

**( TOTAL RUPEES EIGHTY-NINE THOUSAND FIVE HUNDRED EIGHTY-THREE AND SIXTY-TWO PAISE ONLY.)**

**RATE QUOTED BY ME IS : \_\_\_\_\_% (IN WORDS \_\_\_\_\_)**  
**ABOVE/BELOW/AT PAR WITH THE ESTIMATED AMOUNT.**